












Bøyeliste			 IKM Safe Control AS	Tiltakshaver: Høyanger kommune			
			Dato: 17.03.2026	Prosjekt: Hålandselva bru 011			
Post	Tverrsnitt Ø	kg/lm	Skisse	Antall	Kapplengde mm	Σ lengde m	Kg
P1	20	2,47		40	5680	227,2	561,2
P2	12	0,888		76	1380	104,9	93,1
P3	16	1,58		72	1200	86,4	136,5
P4	16	1,58		72	1450	104,4	165,0
P5	16	1,58		24	1250	30,0	47,4
P6	12	0,888		8	1550	12,4	11,0
P7	12	0,888		8	1550	12,4	11,0
P8	12	0,888		28	1130	31,6	28,1
P9	16	1,58		46	500	23,0	36,3
P10	25	3,85		12	1600	19,2	73,9
						Sum kg	1164