



Stangdiameter [mm]		12	16	20	25	32
Forankringslengde [mm]	God heft	300	400	500	700	900
	Dårlig heft	400	600	700	900	1300
Omfangringslengde [mm]	God heft	400	600	700	1000	1400
	Dårlig heft	600	800	1000	1400	1900

01