


Material:
Concrete B45 MF 40 NS-EN 206-1
Reinforcement B500NC NS 3576-3
min. concrete cover: 50mm

Hot dip galvanized bolt, nut, washer steel cl. 8.8

2pcs fixture (1,3t) for lifting ancore in two oposite sides

c-c bolts 240x240mm M20
Capacity:

Mass: 800kg

Designed by Piotr Bakula	Checked by	Approved by	Date 28.09.2021	Date 03.07.2013	
			Betongfundament f/4420 800kg		
			9720547	Edition B	Sheet 1 / 1