












REV.	DATO.	REVISJON.	SIGN.
FORUTSETNINGER			
<ul style="list-style-type: none">• Det monteres egnet brannslange som dekker hele tiltaket• Heledekkende brannalarmanlegg kategori: 2 med alarmoverføring til nedalarmsentral 110• Det monteres ledesystem etter gjeldende regelverk• Alle arealer er sprinklet etter NS-EN 12845			
Branntekniske tegninger må ses i sammenheng med brannteknisk konsept.			
TEGNFORKLARING			
	Rømningsutgang		El 30-Csa [B 30 S]
	Rømningsretning		El 60-Sa [B 60]
	El 60 branncellebegrensende bygningsdel		E 90 [F 90] Heidsør
	Rømningsvei		El 120-Csa A2-s1,d0 [A 120 S]
	Rømningsstråse		Utenfor tiltak
	Tiltaksgrense		
BYGG: Alta kommune			FIRESAFE /
Adresse: Klinikk Alta			
G.nr/B.nr:			
KOMMUNE:			
TEGN. INNHOLD: Brannplan U. etg.			MÅL: 1 : 100
KONTROLT: Bengt S	DATO: 08.01.26	TEGN: Bjørn R	PROSJEKT NR: 1105935
		TEGN.NR: F-20-U	