

When used ProPlay will be reinstalled, it is important to take the following into account. Please read this advice before removing the used ProPlay from its original application:

- Stack the used ProPlay sheets neatly and stably to avoid deformation of the sheets in order to easily reinstall them.
- The pallets on which the ProPlay sheets are stacked must be larger than the net sheet size of 0.90 m x 2.25 m. It is important that the surface of the ProPlay sheet is fully supported.
- The pallets must be placed on a flat and stable surface. How many ProPlay sheets can be placed per pallet depends on the type of ProPlay. For the stability of ProPlay on a pallet, it is recommended not to stack it higher than 1.20 m.
- If the pallets with ProPlay have to be moved (for example from one field to another), the pallets must be secured using at least 3 straps. It is important that the sheets remain in their original form and that these are stacked free of tension.
- If the used ProPlay will not be installed the same day, it must be covered with UV-resistant cover.
- Reinstalling ProPlay must be done according to the ProPlay installation manual. Please note there are separate installation manuals for ProPlay-Sport and ProPlay for playgrounds.

Installation of ProPlay-Sport must be done under the code of good workmanship. Schmitz Foam Products B.V. does not accept any liability for the design, or construction of any facilities, or actions of any parties employed, as a result of, or in connection with, any information provided in this document.

Schmitz Foam Products B.V. is the global supplier of ProPlay®, the perfect shock pad with drainage qualities for high-quality artificial grass systems in sports and playgrounds.



Schmitz Foam Products B.V.
Roermond – The Netherlands
T. +31 (0)475 370 270 • sales@schmitzfoam.com



www.schmitzfoam.com