

Merknader

- 01 8x160mm, SN16
- 02 2x160mm, SN16
- 03 6x160mm, SN16
- 04 4x160mm, SN16
- 05 3x160mm, SN16
- 06 1x160mm, 2x125, SN16
- 07 1x125, 3x75mm, SN16
- 08 1x125, 2x75mm, SN16
- 09 1x125,1x75mm, SN16
- 10 1x125mm
- 11 1x75mm stikk, SN16
- 12 Tilkoblings-/skjøtepunkt
- 13 3x40DL, 1x20DL

Eksisterende wire-hengte armaturer.
LPH = 8m.
Byttes til ny type: Philips BSS563 T25
LED100-4S/730 PSA DM12 eller tilsvarende

Notat:
Alle HS og LS traseer skal ha følgejord 50mm2.

- 14 3x40DL, 2x20DL
- 15 1x125mm SN16, 3x40, 1x20 mm, DL

